



ALUMINUM BODY

MAXIMUM O.A.H. 120.00"

SIDE ROLL AND FRONTAL IMPACT PROTECTION

**NOTE**  
 DIMENSIONS SHOWN ARE APPROXIMATE AND ARE SUBJECT TO MINOR DEVIATIONS AS MAY OCCUR OR BE NECESSARY IN CONSTRUCTION. MINOR DETAILS NOT SHOWN.

- BATTERY CHARGER BEHIND THE OFFICER'S SEAT
- DUAL L.E.D. LIGHT STRIPS LOCATED IN HOSE BED
- DRIP PAN GUARD FOR ROLL-UP DOOR IN L51, L52, L53, B1, R51, R52, AND R53
- ADJUSTABLE FULL WIDTH/DEPTH SHELVES IN TWO IN L53 AND R51 AND ONE IN R53
- ONE ADJUSTABLE TILTING SLIDE-OUT TRAY IN R52 AND R53
- FLOOR MOUNTED SLIDE-OUT TRAYS TWO IN L51 AND ONE IN L53, B1, AND R51
- ALUMINUM TOOLBOARDS MOUNTED TO SLIDE-OUT TRAY TWO IN L51 AND ONE IN L53 AND R51
- TWO POLY TOOL BOXES IN L53 (10" W X 10" D X 24")
- ONE 4-DRAWER CTECH DRAWER ASSEMBLY IN L53
- ONE VERTICAL PARTITION IN R51 AND L53

- CIRCUIT BREAKER PANEL IN L53
- ONE HANNAY ELECTRIC REWIND CORD REEL MODEL 1618-17-18 WITH 150' OF 10/3 CABLE IN P.S. CARGO AREA WITH CIRCLE-D JUNCTION BOX AND TREADPLATE JUNCTION BOX HOLDER AND ROLLERS THRU SIDE
- ONE HORIZONTAL PARTITION IN L53
- ONE POLY MOUNTING BOARD IN L52
- ONSPOT AUTOMATIC TIRE CHAINS TO BE PROVIDED AT THE REAR

REV	DATE	BY	CH	ENFORCER
02MAR20	LST	PPE		PIERCE
29JAN20	LST	PPE		MODEL

		JOB NO.	34268
		SCALE	DATE
TITLE	2000-D-725P W/25G FOAM, 161", FULL HEIGHT & DEPTH (3) X-LAYS, DELUGE, GENERATOR, CABLE REEL		
FOR	CLEVELAND FIRE DEPARTMENT CLEVELAND, TENNESSEE		
DWG NO.	34268AD		
DRAWN BY	LST	DATE	20NOV19
CHECKED BY	NPE	DATE	22NOV19
SHEET SIZE	D	SHEET NO.	1 OF 1