MCloud

Data center Specification



Location	Manchester, UK
Security	 ISO 27001 certified Secure gated compound Restricted access controls Security ID checks and access code CCTV 24/7 access
Power & Environment	 Chilled water system with free cooling ability Cooling SLA: 99.97% Cooling redundancy: N+1 in the DC and 2N on chillers Cold aisle temperature range: 17c to 27c Fire detection: Vesda dual aspirating system Fire suppression system: FM-200 Gas & Novec Highly resilient: A & B power feeds Power SLA: 99.97% Power redundancy: N+1 Generator redundancy: N+1 UPS autonomy: 10 minutes Generator run time: 24hrs
Support	 Engineers on-site: 24/7/365 Remote hands and eyes
Services	 Quarter, half and full rack availability Customer break room & build room facilities Managed services cabling Customer delivery acceptance and storage facilities
Connectivity	 Two Carrier neutral tier 2 & 3 facilities Approximately 40 Peering points across Europe, in addition 50 (approx.) private peering points globally International capabilities - one of the world's largest privately owned connectivity network, with Terabit connectivity across Europe Network Info https://www.peeringdb.com/asn/9009

TSDC0219V2

