## COMFORT CLUB MEMBERSHIP



\$17.95 per month for the first system\* and \$9 per month for each additional system

Your Comfort Club Membership guarantees appointments, provides valuable services and discounts on repairs. You are guaranteed that your repair is "Fixed Right or It's FREE." As a Comfort Club Member, you are guaranteed:

• Appointments in 24 hours

- Program thermostat to customers' needs

- 2 Complimentary Precision Tune-Ups
- 15% discount on IAQ products

- \$69 service fee day or night
- 15% discount on repairs
- \*One system includes heating & cooling

AIR CONDITIONING / HEAT PUMP	FURNACE, AIR HANDLER, CONTRO	OLS
<ul> <li>Check compressor amps</li> <li>Check condenser fan amps/condition</li> <li>Check capacitor uF value</li> <li>Inspect contactor</li> <li>Check Indoor WB/Outdoor Temp</li> <li>Tighten wire connections</li> <li>Check start assist device</li> <li>Test defrost timer operation</li> <li>Test reversing valve operation</li> <li>Check condition of coil fins</li> <li>Check O-ring Schrader caps</li> <li>Check electrical disconnect</li> <li>Tighten lugs in disconnect &amp; circuit breaker</li> <li>Check low voltage wire condition</li> <li>Check condensing unit is level</li> <li>Check line set insulation</li> </ul>	<ul> <li>Check flame sensor / CAD cell</li> <li>Check Return &amp; Supply static pressure</li> <li>Check evaporator coil</li> <li>Inspect start collar seal</li> <li>Inspect blower cabinet insulation</li> <li>Inspect blower wheel</li> <li>Inspect flue pipe</li> <li>Inspect all electrical</li> <li>Check circuit board</li> <li>Check blower bearings</li> <li>Check TXV bulb mount</li> <li>Inspect oil tanks and lines</li> <li>Check primary &amp; secondary drains</li> <li>Check condensate pump</li> <li>Inspect drain safety switch</li> <li>Check pan</li> <li>Replace missing screws</li> <li>Read blower motor amps</li> <li>Check inducer motor amps</li> <li>Check blower capacity uF value</li> </ul>	<ul> <li>Measure temp rise</li> <li>Adjust gas pressure</li> <li>Check limit switches and mounts</li> <li>Check crossover burner ports</li> <li>Vacuum furnace area and burners</li> <li>Check combustion air vent screen</li> <li>Inspect heat exchanger</li> <li>Check hoses for cracks and wear</li> <li>Check pressure switch</li> <li>Measure flue rise &amp; clearances</li> <li>Check flue pipe for leaks and rust</li> <li>Inspect PVC for leaks, etc.</li> <li>Test gas connections for leaks</li> <li>Check proper ignition</li> <li>Run furnace in all stages</li> <li>Test gas shut off operation</li> <li>Clean/wax outside of the furnace</li> <li>Filter change/clean (standard size)</li> </ul>
THERMOSTAT	HYDRONICS	
<ul><li>Check batteries (homeowner supplied)</li><li>Check thermostat mount</li></ul>	- Test low water cut off - Test auto feeder	

Check Aquastat and settingsCheck pressure-temperature gauge

- Test circulators / oil / couplings

Check tempering mix valve

- Check expansion tank / pressure relief valve

- Check for leaks on exterior components